

**SURVEY &  
REMONUMENTATION**

OCT 29 1996

COMMISSION

REMONUMENTATION

*Re-Monumentation, Page 16*

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Paris T15N R14E	I-13, J-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED  
10 SEP 96 8:41 A.M.  
FRANCES L. HOLDWICK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Charles S. Getz, in a field survey on July 2, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-13 GLO Notes  
Set Post at 80.00 Chains  
Sugar 20", N75°W, 11 Links  
Sugar 16", N30°E, 15 Links  
County Surveyor's Record - Large Rock just .55 North of Ford Axle, Act 74 - None, Act 132 - None
- J-13 GLO Notes  
Set 1/4 Cor at 40.00 Chains  
Elm 7", N40°E, 3 Links  
Hemlock 7", N13°W, 91 Links  
County Surveyor's Record - 3/4" Iron Pin 1.0 North of Large Stone, Act 74 - None, Act 132 - None, Unrecorded Survey dated 5-23-95 by Case Surveying

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-13  
SW Cor, Section 35, T15N-R14E  
Found Monument Box in Asphalt Road (Intersection of Huron Line Road and Parisville Road)  
APPROVED PEER BOARD MEETING  
RLB Sept 9, 1996
- J-13  
S 1/4 Cor, Sec 35, T15N-R14E  
Found Railroad Spike, 6" Deep, in Gravel Road Bed (Huron Line Road)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-13  
SW Cor, Section 35, T15N-R14E  
Mounment Box in Asphalt Road  
West 20.46' to Mounment Box  
S50°W 52.75' to Road Sign  
S45°E 42.92' to Concrete Project Marker  
N45°W 56.40' to Concrete Project Marker  
West 2638.76' to S 1/4 Cor, Sec 34, T15N-R14E  
East 2642.46' to S 1/4 Cor, Sec 35, T15N-R14E
- J-13  
S 1/4 Cor, Section 35, T15N-R14E  
Railroad Spike in Gravel Road Bed  
North 53.65' to Nail in E. Side of Power Pole  
N30°W 40.90' to West End of 24" C.M.P.  
North 198.83' to Nail in E. Side of 24" Ash  
West 2642.46' to SW Cor, Sec 35, T15N-R14E  
East 2610.50' to SE Cor, Sec 35, T15N-R14E

Signed by Charles S. Getz  
Surveyor's Michigan License No. 25843

Date July 15, 1996

