

**SURVEY &
REMONUMENTATION**

APR 27 1995

REMONUMENTATION
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Re-Mon. Liber 1, Page 1

For corners in

Huron (County)	Located In:	Corner Code #/
1. Public Land Survey	T 15 N R 15 E	A-1, A-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
HURON COUNTY
RECORDED

1 NOV 94 3:45 P.M.

FRANCES L. HOLLOWICK
REGISTER OF DEEDS
Stamp & File Number

I, Charles S. Getz, in a field survey on August 19, 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- A-1 Found Monu Box in Asphalt at Intersection of Helena Road and Finkle Road over former location of 3/4" Pin as recorded in Liber 3 of Surveys, Page 82, Huron County Records, said survey dated 10-25-76, by Huron Surveying, Inc.
 - A-2 Found 5/8" Bar in gravel road bed (Finkle Road). Raised with 1/2" Iron Bar. GLO Notes were researched. Huron County Road Commission notes & County Surveyor records show no evidence of Corner.

Approved at Peer Board Meeting,
1994 10-10-94
Russell L. Brown

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-1
NW Cor, Section 6, T15N-R15E
Found Monu Box
- A-2
W 1/4 Cor, Section 6, T15N-R15E
Found 5/8" Iron Bar



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| <p>A-1
NW Cor, Section 6, T15N-R15E
Monu Box
N35°E 89.25' to Spike in Brace Pole
N45°W 71.95' to Spike in Power Pole
S45°W 66.66' to Spike in Power Pole
S45°E 64.75' to Spike in GTE Box Post
South 2693.94' to W 1/4 Cor, Section 6,
T15N-R15E</p> | <p>A-2
W 1/4 Cor, Section 6, T15N-R15E
1/2" Iron Bar
East 4.0' to Centerline of Gravel Road
S85°E 47.65' to Spike in Power Pole
S45°W 40.30' to Notch in North End of 48" CMP
S30°W 67.50' to Notch in South End of 48" CMP
North 2693.94' to NW Cor, Section 6,
T15N-R15E.
South 2632.04' to SW Cor, Section 6,
T15N-R15E</p> |
|--|--|

Signed by Charles S. Getz Date August 30, 1994
Surveyor's Michigan License No. 25843