

**SURVEY & REMONUMENTATION**

APR 27 1995

REMONUMENTATION COMMISSION

For corners in

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

*Re - Mon. Leber 1, Page 2*

1 NOV 94 3:45 P.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

<u>Huron</u> <small>(County)</small>	Located In:	Corner Code <del>##</del>
1. Public Land Survey	T <u>15</u> NR <u>15</u> E	<u>A-3, A-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Charles S. Getz, in a field survey on August 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- A-3 Found 1" Iron Bar in Gravel Road Bed at Intersection of Purdy Road and Finkle Road as per Huron County Road Commission notes. Raised with 1/2" Iron Bar.
- A-4 Found 3/4" Iron Bar in Gravel Road Bed (Finkle Road) as per Huron County Road Commission notes.

Approved at Peer Board Meeting,  
1994 10-10-94  
*Russell L Brown*

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- A-3  
NW Cor, Section 7, T15N-R15E  
Found 1" Iron Bar
- A-4  
W 1/4 Cor, Section 7, T15N-R15E  
Found 3/4" Iron Bar



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |   |
|--|---|
| <p>A-3<br/>NW Cor, Section 7, T15N-R15E<br/>1/2" Iron Bar<br/>N45°E 72.50' to Spike in Power Pole<br/>N30°W 82.30' to Southeast Corner of Retainer Wall<br/>N45°W 117.40' to Southeast Corner of Barn<br/>S45°E 43.00' to Notch in East End of 48" CMP<br/>North 2632.04' to W 1/4 Cor, Section 6, T15N-R15E<br/>South 2638.75' to W 1/4 Cor, Section 7, T15N-R15E</p> | <p>A-4<br/>W 1/4 Cor, Section 7, T15N-R15E<br/>3/4" Iron Bar<br/>East 7.0' to Centerline of Gravel Road<br/>West 22.50' to Spike in 15" Ash Tree<br/>N15°W 64.40' to Spike in Tripple Ash Tree<br/>S15°W 35.80' to Spike in Double Ash Tree<br/>North 2638.75' to NW Cor, Section 7, T15N-R15E<br/>South 2635.29' to SW Cor, Section 7, T15N-R15E</p> |
|--|---|

Signed by Charles S. Getz  
Surveyor's Michigan License No. 25843

Date August 30, 1994