

SURVEY & REMONUMENTATION COMMISSION

APR 27 1995

Re - Mon. Liber 1, Page 2

STATE OF MICHIGAN
HURON COUNTY
RECORDED

REMONUMENTATION COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1 NOV 94 3:45 P.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15</u> NR <u>15</u> E	A-3, <u>A-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Charles S. Getz, in a field survey on August 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3 Found 1" Iron Bar in Gravel Road Bed at Intersection of Purdy Road and Finkle Road as per Huron County Road Commission notes. Raised with 1/2" Iron Bar.

A-4 Found 3/4" Iron Bar in Gravel Road Bed (Finkle Road) as per Huron County Road Commission notes.

Approved at Peer Board Meeting,
1994 10-10-94
Russell L. Brown

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3
NW Cor, Section 7, T15N-R15E
Found 1" Iron Bar

A-4
W 1/4 Cor, Section 7, T15N-R15E
Found 3/4" Iron Bar



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3
NW Cor, Section 7, T15N-R15E
1/2" Iron Bar
N45°E 72.50' to Spike in Power Pole
N30°W 82.30' to Southeast Corner of Retainer Wall
N45°W 117.40' to Southeast Corner of Barn
S45°E 43.00' to Notch in East End of 48" CMP
North 2632.04' to W 1/4 Cor, Section 6;
T15N-R15E
South 2638.75' to W 1/4 Cor, Section 7;
T15N-R15E

A-4
W 1/4 Cor, Section 7, T15N-R15E
3/4" Iron Bar
East 7.0' to Centerline of Gravel Road
West 22.50' to Spike in 15" Ash Tree
N15°W 64.40' to Spike in Tripple Ash Tree
S15°W 35.80' to Spike in Double Ash Tree
North 2638.75' to NW Cor, Section 7,
T15N-R15E
South 2635.29' to SW Cor, Section 7,
T15N-R15E

Signed by Charles S. Getz Date August 30, 1994
Surveyor's Michigan License No. 25843