

**SURVEY &  
REMONUMENTATION**

APR 27 1995  
REMONUMENTATION  
COMMISSION

*Re-Mon. Liber 1, Page 5*

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>15</u> N R <u>15</u> E	<u>A-9</u> , A-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

1 NOV 94 3:46 P.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Charles S. Getz, in a field survey on August 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

**A. Description of original monument and accessories and/or subsequent restoration:**

A-9 Found Monu Box in Asphalt at Intersection of Atwater Road and Finkle Road as recorded in Liber 3 of Surveys, Page 141, Huron County Records, said survey dated 5-26-76, by Huron Surveying, Inc.

A-10 Found No Evidence of an Existing Corner at site. Corner was a 1/2" Iron Bar on 5-26-76, as per a previous survey being Recorded in Liber 3 of Surveys, Page 141, Huron County Records, said survey by Huron Surveying, Inc. A spike in a power pole, as called for in said survey, is only Witness remaining.

Approved at Peer Board Meeting,

1994 10-10-94

*Russell L. Down*

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-9  
NW Cor, Section 30, T15N-R15E  
Found Monu Box

A-10  
W 1/4 Cor, Section 30, T15N-R15E  
Set 1/2" Iron Bar. Corner was Re-Established by using a Found Property Corner, and the Bearings and Distances shown on a previous survey, as Recorded in Liber 3 of Surveys, Page 141, Huron County Records, said survey dated 5-26-76, by Huron Surveying, Inc.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-9  
NW Cor, Section 30, T15N-R15E  
Monu Box  
S45°W 67.70' to Nail in 24" Ash Tree  
N45°W 51.78' to Southeast Cor of 12" Concrete Post  
N45°E 66.30' to Spike in Telephone Pole  
S55°E 103.30' to Spike in Power Pole  
North 2644.86' to W 1/4 Cor, Section 19, T15N-R15E  
South 2644.14' to W 1/4 Cor, Section 30, T15N-R15E

A-10  
W 1/4 Cor, Section 30, T15N-R15E  
1/2" Iron Bar  
S65°W 62.32' to Spike in Power Pole  
S30°E 115.80' to Face of Buried Cable Post  
North 2644.14' to NW Cor, Section 30, T15N-R15E  
South 2644.14' to SW Cor, Section 30, T15N-R15E

Signed by Charles S. Getz

Date August 31, 1994

Surveyor's Michigan License No. 25843