

SURVEY & REMONUMENTATION

APR 27 1995

REMONUMENTATION COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

Re-Mon. Liber 1, Page 7

For corners in

<u>Huron</u> (County)	Located In:	Corner Code <i>≠</i>
1. Public Land Survey	T <u>15</u> NR <u>15</u> E	<u>A-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1 NOV 94 3:46 P.H.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Charles S. Getz, in a field survey on August 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-13 Found 1-1/2" Pipe in Gravel Road Bed at Intersection of Huron Line Road and Finkle Road. Huron County Road Commission notes call for "3/4 inch Iron Pin In The Center Of Grades". 1-1/2" Iron Pipe is in the center of both gravel road grades of the afore said roads. A search of the entire road intersection was conducted, and only the 1-1/2" Iron Pipe was found.

Approved at Peer Board Meeting
1994 *Russell L. Proen*
10-10-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13
SW Corner, Section 31, T15N-R15E
Found 1-1/2" Iron Pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13
SW Corner, Section 31, T15N-R15E
1-1/2" Iron Pipe
N45°W 72.75' to Spike in Power Pole
N45°E 61.20' to Spike in Power Pole
S45°E 40.75' to Spike in Old Corner Post
N50°E 46.80' to Top Center of Telephone Box
North 2629.00' to W 1/4 Cor, Section 31,
T15N-R15E



Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date September 1, 1994