

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Re-Mon Liber 1, Page 41

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T15N R15E	<u>B-13</u> C-13
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN
HURON COUNTY
RECORDED

7 NOV 96 1:56 P.M.

FRANCES L. HOLLOWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on 9-13, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13	●	●										

A. Description of original monument and accessories and/or subsequent restoration:

B-13 GLO Notes County Survey Record
Set 1/4 Section Post Large Stone Pin East Side
Hemlock 10 N71W 28 Act 74 None Act 132 None
Cedar 10 N27E 28

C-13 GLO Notes Act 132 Liber 1 Page 116
80.00 Set Post Cor Section County Survey Record Iron Pipe
Elm8 N45E 14 Act 74 None
Poplar N87W 18 State Highway Right of Way Book

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13
S 1/4 Corner Section 31 T15N-R15E
Found 1" Pipe in gravel Road Bed
Fence to North

C-13
SE Corner Section 31 T15N-R15E
Found Monu Box

APPROVED PEER BOARD MEETING
Oct 29, 1996

John A. Milletics

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13	C-13
S 1/4 Corner Section 31 T15N-R15E	SE Corner Section 31 T15N-R15E
1" Iron Bar in Gravel Road Bed	Monu Box Centerline of Pavement with Capped 1/2" Pin
North 34.90 to a nail in a Fence Post	N45°E 79.00 to a nail in a Power Pole
N10°W 83.00 to a nail in a 6" Catalpa	N45°W 71.90 to a nail in a Anchor Pole
N20°W 36.00 to a nail in a Fence Post	S45°W 67.15 to a nail in a Tele Pole
N30°W 87.80 to a nail in a 12 Catalpa	S45°E 47.85 to the SE Corner of a Conc Headwall
West 2431.44' to SW Cor	West 2637.10' to S 1/4 Cor
East 2637.10' to SE Cor	East 2638.22' to S 1/4 Cor

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date Oct 11, 1996

