

**SURVEY &
REMONUMENTATION**

DEC 16 1996

COMMISSION

Re-Monument 1, Page 39

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>15E</u>	<u>D-13</u> E-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
HURON COUNTY
RECORDED
7 NOV 96 1:55 P.M.
FRANCES L. HOLDWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on 9-17, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-13 GLO Notes 40.00 Set 1/4 Section Post Elm 9 N62E 18 Hemlock 9 N64W 19	Act 132 None Act 74 None. County Survey Record Iron Pin Unrecorded Survey Dated April 1992
E-13 GLO Notes Set Post Corner Section Hemlock 13 N77½E 20 Sugar 16 N65½W 31	Act 132 None Act 74 None County Survey Records Pin in Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 S 1/4 Corner Section 32 T15N-R15E
Set Corner in Line with N 1/4 Cor
at Half Distance.

E-13 SE Corner Section 32 T15N-R15E
Found Monu Box in Centerline of Pavement

APPROVED PEER BOARD MEETING
Oct 29, 1996

John A. Milletics

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 S 1/4 Corner Section 32 T15N-R15E Monu Box in pavement with capped 1/2" Pin East 10.69 to a Monu Box S20°E 35.70 to a Metal Post S60°W 134.10 to NE Cor of House N60°W 96.90 to a nail in a Power Pole West 2638.22' to SW Cor East 2638.22' to SE Cor	E-13 SE Corner Section 32 T15N-R15E Monu Box in Centerline of Pavement with capped 1/2" Pin East 26.40 to a Monu Box S45°E 57.05 to a Bell Box N45°E 54.95 to a Metal Post N45°W 70.35 to a nail in a Power Pole West 2638.22 to S 1/4 Cor East 2644.60 to S 1/4 Cor
---	--

Signed by *John A. Milletics*
Surveyor's Michigan License No. 25859

Date 10-11-96

