

**SURVEY &  
REMONUMENTATION**

DEC 16 1996

COMMISSION

*Re-Monumentation, Page 39*

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>15E</u>	D-13 E-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED  
  
7 NOV 96 1:55 P.M.  
  
FRANCES L. HOLIDWICK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on 9-17, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- D-13 GLO Notes Act 132 None Act 74 None.  
40.00 Set 1/4 Section Post County Survey Record Iron Pin  
Elm 9 N62E 18 Unrecorded Survey Dated April 1992  
Hemlock 9 N64W 19
- E-13 GLO Notes Act 132 None Act 74 None  
Set Post Corner Section County Survey Records Pin in Post  
Hemlock 13 N77½E 20  
Sugar 16 N65½W 31

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- D-13 S 1/4 Corner Section 32 T15N-R15E  
Set Corner in Line with N 1/4 Cor  
at Half Distance.
- E-13 SE Corner Section 32 T15N-R15E  
Found Monu Box in Centerline of Pavement

APPROVED PEER BOARD MEETING  
Oct 29, 1996

*John A. Milletics*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |   |
|---|---|
| D-13                                      | E-13  |
| S 1/4 Corner Section 32 T15N-R15E         | SE Corner Section 32 T15N-R15E                          |
| Monu Box in pavement with capped 1/2" Pin | Monu Box in Centerline of Pavement with capped 1/2" Pin |
| East 10.69 to a Monu Box                  | East 26.40 to a Monu Box                                |
| S20°E 35.70 to a Metal Post               | S45°E 57.05 to a Bell Box                               |
| S60°W 134.10 to NE Cor of House           | N45°E 54.95 to a Metal Post                             |
| N60°W 96.90 to a nail in a Power Pole     | N45°W 70.35 to a nail in a Power Pole                   |
| West 2638.22' to SW Cor                   | West 2638.22 to S 1/4 Cor                               |
| East 2638.22' to SE Cor                   | East 2644.60 to S 1/4 Cor                               |

Signed by *John A. Milletics*  
Surveyor's Michigan License No. 25859

Date 10-11-96

