

**SURVEY &  
REMONUMENTATION**

DEC 1 8 1996

COMMISSION

*Re-Monument 1, Page 36*

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>15E</u>	<u>J-13</u> K-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

7 NOV 96 1:55 P.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on 9-24, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-13 GLO Notes Act 132 None, Act 74 None  
Set 1/4 Section Post 40.00 No County Survey Record  
Poplar 16 N78W 7 1/2  
Cedar 9 N55E 8

K-13 GLO Notes Act 132 None, Act 74 None  
80.00 Set Post Corner County Survey record shows Axle  
Hemlock 10 N58E 34 1/2  
Hemlock 13 N40W 17

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13  
S 1/4 Corner Section 35 T15N-R15E  
Set 1/2 Iron Bar on line between SE and SW Corner of Section at half distance  
iron is due south of large post corner

K-13  
SE Corner Section 35 T15N-R15E  
Found 1/2" Iron Bar in Gravel Road Bed

APPROVED PEER BOARD MEETING  
Oct 29, 1996

*John A. Milletics*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13  
S 1/4 Corner Section 35 T15N-R15E  
1/2" Iron Bar in gravel Road Bed  
North 33.60 to a nail in a Large Fence Post  
North 44.50 to a nail in a Fence Post  
S20°W 38.37 to a Bell Box  
N20°E 93.82 to a nail in a 8" Ash  
West 2636.56' to SW Cor  
East 2636.56' to SE Cor

K-13  
SE Corner Section 35 T15N-R15E  
1/2" Iron Bar in Gravel Road Bed  
S45°E 55.80 to a nail in a Power Pole  
N45°E 70.80 to a nail in a Power Pole  
N45°W 45.35 to a Road Sign  
S30°W 41.20 to a Bell Box  
West 2636.56 to S 1/4 Cor  
East 2631.80 to S 1/4 Cor

Signed by John A. Milletics  
Surveyor's Michigan License No. 25859

Date Oct 25, 1996

