

**SURVEY &
MONUMENTATION**

DEC 1 8 1996

COMMISSION

Re-Monument 1, Page 36

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Huron (County) Located In: Corner Code #

1. Public Land Survey T 15N R 15E J-13 K-13
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
 S ___ T ___ R ___

STATE OF MICHIGAN
HURON COUNTY
RECORDED
7 NOV 96 1:55 P.M.
FRANCES L. HOLDWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John A. Millettics, in a field survey on 9-24, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-13 GLO Notes Act 132 None, Act 74 None
 Set 1/4 Section Post 40.00 No County Survey Record
 Poplar 16 N78W 7 1/2
 Cedar 9 N55E 8

K-13 GLO Notes Act 132 None, Act 74 None
 80.00 Set Post Corner County Survey record shows Axle
 Hemlock 10 N58E 34 1/2
 Hemlock 13 N40W 17

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13
 S 1/4 Corner Section 35 T15N-R15E
 Set 1/2 Iron Bar on line between SE and SW Corner of Section at half distance
 iron is due south of large post corner

K-13
 SE Corner Section 35 T15N-R15E
 Found 1/2" Iron Bar in Gravel Road Bed

APPROVED PEER BOARD MEETING
 Oct 29, 1996

John A. Millettics

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13
 S 1/4 Corner Section 35 T15N-R15E
 1/2" Iron Bar in gravel Road Bed
 North 33.60 to a nail in a Large Fence Post
 North 44.50 to a nail in a Fence Post
 S20°W 38.37 to a Bell Box
 N20°E 93.82 to a nail in a 8" Ash
 West 2636.56' to SW Cor
 East 2636.56' to SE Cor

K-13
 SE Corner Section 35 T15N-R15E
 1/2" Iron Bar in Gravel Road Bed
 S45°E 55.80 to a nail in a Power Pole
 N45°E 70.80 to a nail in a Power Pole
 N45°W 45.35 to a Road Sign
 S30°W 41.20 to a Bell Box
 West 2636.56 to S 1/4 Cor
 East 2631.80 to S 1/4 Cor

Signed by John A. Millettics
 Surveyor's Michigan License No. 25859

Date Oct 25, 1996

