

Re - Mon Liber 1, Page 35

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in HURON Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey	T 15N R 15E	<u>L-13</u> M-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED
 7 NOV 96 1:55 P.M.
 FRANCES L. HOLDWICK
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A. Millettics, in a field survey on 9-24, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- L-13 GLO Notes Act 132 None, Act 74 None
 40.00 Set 1/4 Section Post County Survey Record None
 Hemlock 15 N87E 29
 Hemlock 15 N41 1/2 W 23
 - M-13 GLO Notes Act 132 None, Act 74 None
 80.00 Set Post Corner County Survey Record - Large Iron Pin
 Hemlock 10 N58E 34 1/2
 Hemlock 13 N40W 17

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- L-13
 S 1/4 Corner Section 36 T15N-R15E
 Set 1/2 Iron Bar on Line Between SE and SW Corner of Section at half distance
 - M-13 SE Corner Section 36 T15N-R15E
 Found 1" Pipe in Gravel Road Bed

APPROVED PEER BOARD MEETING
 Oct 29, 1996
John A. Millettics

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- L-13
 S 1/4 Corner Section 36 T15N-R15E
 1/2" Iron Bar
 N05°E 34.98 to a nail in a Fence Post
 N30°E 48.25 to a nail in a Power Pole
 North 7.50 to the centerline of Gravel Road
 S45°W 32.35 to a Bell Box
 West 2631.80' to SW Cor
 East 2631.80' to SE Cor
 - M-13
 SE Corner Section 36 T15N-R15E
 1" Pipe
 East 31.15 to a nail in a Tele Post
 S85°E38.70 to a nail in a Fence Post
 S75°E 40.65 to a nail in a Fence Post
 N45°W 38.70 to a Road Sign
 S45°W 41.60 to a Stop Sign
 West 2631.80 to S 1/4 Corner



Signed by *John A. Millettics*
 Surveyor's Michigan License No. 25859

Date Oct 25, 1996