

DEC 1 8 1996

COMMISSION

Re-Monumentation, Page 35

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: HURON (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

STATE OF MICHIGAN
HURON COUNTY
RECORDED
7 NOV 96 1:55 P.M.
FRANCES L. HOLDWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, John A. Milletics, in a field survey on 9-24, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numerical data for survey points.

- A. Description of original monument and accessories and/or subsequent restoration:
L-13 GLO Notes Act 132 None, Act 74 None
40.00 Set 1/4 Section Post County Survey Record None
Hemlock 15 N87E 29
Hemlock 15 N41 1/2 W 23
M-13 GLO Notes Act 132 None, Act 74 None
80.00 Set Post Corner County Survey Record - Large Iron Pin
Hemlock 10 N58E 34 1/2
Hemlock 13 N40W 17

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
L-13
S 1/4 Corner Section 36 T15N-R15E
Set 1/2 Iron Bar on Line Between SE and SW Corner of Section at half distance

M-13 SE Corner Section 36 T15N-R15E
Found 1" Pipe in Gravel Road Bed

APPROVED PEER BOARD MEETING
Oct 29, 1996

Handwritten signature of John A. Milletics

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13
S 1/4 Corner Section 36 T15N-R15E
1/2" Iron Bar
N05°E 34.98 to a nail in a Fence Post
N30°E 48.25 to a nail in a Power Pole
North 7.50 to the centerline of Gravel Road
S45°W 32.35 to a Bell Box
West 2631.80' to SW Cor
East 2631.80' to SE Cor

M-13
SE Corner Section 36 T15N-R15E
1" Pipe
East 31.15 to a nail in a Tele Post
S85°E38.70 to a nail in a Fence Post
S75°E 40.65 to a nail in a Fence Post
N45°W 38.70 to a Road Sign
S45°W 41.60 to a Stop Sign
West 2631.80 to S 1/4 Corner

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date Oct 25, 1996

