

SURVEY & REMONUMENTATION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Re-Monument 1, Page 75

JAN 22 1998

For corners in

Huron	SECTION	Located In:	Corner Code #
(County)			
1. Public Land Survey	Sherman	T15N R16E	A-13
		T R	B-13
		T R	
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED

6 NOV 97 10:26 A.M.

FRANCES L. HOLDWICK
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Charles S. Getz, in a field survey on Nov. 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- A-13 1834 G.L.O., H. Parke D.S. County Surveyor Records - NONE, Co. Rd. Comm. Records - NONE
 Post Recorded Surveys - NONE Unrecorded Surveys - NONE
 Beech 16", S70°E, 11½ Links L.C.R.C. 1996 Remonumentation - 1" Pipe
 do. 16", N31°W, 4 Links
- B-13 1834 G.L.O., H. Parke D.S. County Surveyor Records - NONE Co. Rd. Comm. Records - NONE
 Set quarter section post Recorded Surveys - NONE Unrecorded Surveys - NONE
 Sugar 18", N48°W, 35 Links L.C.R.C. - NONE
 Beech 6", N35°E, 25 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-13 SW Cor, Section 31, T15N-R16E Found 1" Pipe Accepted as the best available evidence of original corner position (Intersection of Huron Line & Edwards Roads)
- B-13 S 1/4 Cor, Section 31, T15N-R16E Found no evidence of original corner position. Re-established corner position by proportionate measure from G.L.O. Notes, between C-13 and A-13 as best evidence of original corner position for B-13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-13 SW Cor, Section 31, T15N-R16E Found 1" Pipe East 31.15' to Nail in N. Side of Tele Pole S85°E 38.70' to Nail in S. Side of Fence Post S75°E 40.65' to Nail in S. Side of Fence Post N45°W 38.70' to Road Sign S45°W 41.60' to Stop Sign West 2631.80' to S 1/4 Cor, Sec 36, T15N-R15E East 2631.04' to S 1/4 Cor, Sec 31, T15N-R16E
- B-13 S 1/4 Cor, Section 31, T15N-R16E Set 1/2" Re-Rod (Capped) N70°W 4.74' to Nail in 12" Apple Tree West 12.10' to Nail in 12" Birch S50°W 12.20' to Nail in 12" Birch East 20.15' to Nail in 18" Birch West 2631.04' to SW Cor, Sec 31, T15N-R16E East 2631.04' to SE Cor, Sec 31, T15N-R16E

Signed by Charles S. Getz
 Surveyor's Michigan License No. 25843

Date November 4, 1997

PEER GROUP APPROVED AT MEETING November 5, 1997.

RLB

