

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Re-Mow Liber 1, Page 76

For corners in

Huron	Located In:	Corner Code #
(County)		
1. Public Land Survey Sherman	T15N R16E	C-13
	T R	D-13
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
HURON COUNTY
RECORDED

6 NOV 97 10:27 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Charles S. Getz, in a field survey on Nov. 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-13 1834 G.L.O., H. Parke D.S. Set Post Beech 12", N20½°E, 5½ Links do. 8", N76°W, 27 Links	Co. Surveyor Records - NONE Survey Liber 5, Page 171 - 1-1/2" Iron Pipe Case Surveying - 1-1/2" Iron Pipe Plat of "SUMMER HAVEN" Liber 5, Page 25 - shows corner	Co. Rd. Comm. Records - NONE
D-13 1834 G.L.O., H. Parke D.S. Set quarter section post Hemlock 20", N76°E, 26½ Links do. 7", N39°W, 8 Links	Co. Surveyors Records - NONE Recorded Surveys - NONE L.C.R.C. - NONE	Co. Rd. Comm. Records - NONE Unrecorded Surveys - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 SW Cor, Section 32, T15N-R16E Found 5/8" Iron Bar Accepted as the best available evidence of original corner position	D-13 S 1/4 Cor, Section 32, T15N-R16E Found no evidence of original corner position. Re-established corner position by using G.L.O. Notes for distance, and monumentation of "SUMMER HAVEN" plat for line. Said Plat Recorded in Liber 5 of Plats, Page 25
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 SW Cor, Section 32, T15N-R16E Fd 5/8" Iron Bar North 32.60' to Nail in Fence Post N45°W 41.00' to Nail in Fence Post S20°W 46.60' to Nail in 24" Maple S50°E 54.00' to Nail in 18" Maple West 2631.04' to S 1/4 Cor, Sec 31, T15N-R16E East 2640.00' to S 1/4 Cor, Sec 32, T15N-R16E	D-13 S 1/4 Cor, Section 32, T15N-R16E Set 1/2" Re-Rod (Capped) N45°E 93.80' to Southwest Corner of House West 6.70' to Nail in Power Pole West 53.50' to Nail in 24" Poplar S75°E 71.00' to Nail in 6" Birch West 321.20' to East Road Right of Way Line of U.S. 25 West 2640.00' to SW Cor, Sec 32, T15N-R16E
---	--

Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date November 4, 1997

PEER GROUP APPROVED AT
MEETING November 5, 1997
RLB

