

JAN 19 2001

2000 REMONUMENTATION

Re-Monumented, Page 76

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Sherman T15N R16E	A-3
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
HURON COUNTY
RECORDED

20 SEP 2000 2:05 PM

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Charles S. Getz, in a field survey on May 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:


A-3 1834 G.L.O., H. Parke D.S. County Road Commission Records - Iron Pin
 Set Post
 Birch 12", N35°W, 27 Links Recorded Surveys - Case, 3-6-74, Liber 2, Page 29,
 do. 11", S29½°W, 32½ Links Certificate shows Corner
 Brown, 8-22-78, Liber 3, Page 676, 1" Pipe
 L.C.R.C. - NONE
 Unrecorded Surveys - Brown, 12-30-87, 1" Pipe
 County Surveyor Records - Brown, 12-14-88, 1" Pipe
 NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3
 SW Cor, Section 6, T15N-R16E
 Found 1-1/2" Pipe
 Accepted as the best available evidence
 of the original corner position
 (Intersection of Purdy Road & Edwards Road)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3
 SW Cor, Section 6, T15N-R16E
 Found 1-1/2" Pipe
 N45°W 45.6' to Nail in Telephone Pole
 S45°E 71.5' to Nail in Power Pole
 N45°E 40.4' to Stop Sign
 S45°W 33.8' to Stop Sign
 S30°W 33.7' to West End of 18" C.M.P.
 S30°E 35.7' to East End of 18" C.M.P.
 South 2633.66' to W 1/4 Cor, Sec 7, T15N-R16E
 North 2629.52' to W 1/4 Cor, Sec 6, T15N-R16E



Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date June 3, 2000

PEER GROUP APPROVED AT MEETING
HELD September 18, 2000. RLB