

JAN 19 2001

Re-man Liked 2, Page 80

2000 REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Huron (County)	Located in:	Corner Code #
1. Public Land Survey	Sherman T15N R 16E	A-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
HURON COUNTY
RECORDED

20 SEP 2000 2:06 PM

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													


I, Charles S. Getz, in a field survey on May 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A-7 1834 G.L.O., H. Parke D.S. County Road Commission Records - 3/4" Iron Pin
Set Post
Henlock 12", N54°W, 16 Links Recorded Surveys - NONE
do. 10", S52 1/2°W, 2 1/2 Links Unrecorded Surveys - NONE
L.C.R.C. - NONE

County Surveyor Records - NONE
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-7
SW Cor, Section 18, T15N-R16E
Found 1/2" Iron Bar
Accepted as the best available evidence of the original corner position (Intersection of Leppok Road & Edwards Road)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-7
SW Cor, Section 18, T15N-R16E
Found 1/2" Iron Bar
S45°E 45.65' to Nail in Telephone Pole
N45°E 36.80' to Stop Sign
S45°W 34.0' to Stop Sign
S30°E 34.8' to West End of 24" C.M.P.
S40°E 33.4' to East End of 24" C.M.P.
South 2637.24' to W 1/4 Cor, Sec 19, T15N-R16E
North 2623.69' to W 1/4 Cor, Sec 18, T15N-R16E



Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date June 3, 2000

PEER GROUP APPROVED AT MEETING
HELD September 18, 2000 *RUB*