

JAN 19 2001

2000 REMONUMENTATION. *Re Mon Liber 2, Page 81*

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	Sherman T15N R16E	A-8
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

20 SEP 2000 2:07 PM

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Charles S. Getz, in a field survey on May 10, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-8 1834 G.L.O., H. Parke D.S. County Road Commission Records - Iron Pin  
Set quarter section post  
Beech 10", S4°W, 21 1/2 Links Recorded Surveys - NONE  
Hemlock 9", N21°W, 20 Links Unrecorded Surveys - NONE  
L.C.R.C. - NONE

County Surveyor Records - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8  
W 1/4 Cor, Section 19, T15N-R16E  
Found 1/2" Iron Bar  
Accepted as the best available evidence of the original corner position (On Edwards Road)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8  
W 1/4 Cor, Section 19, T15N-R16E  
Found 1/2" Iron Bar  
N45°W 56.18' to Nail in Power Pole  
S85°W 35.0' to Nail in 18" Ash  
S40°W 49.55' to Nail in 12" Ash  
S20°W 74.0' to Nail in 12" Ash  
South 2638.45' to SW Cor, Sec 19, T15N-R16E  
North 2637.24' to NW Cor, Sec 19, T15N-R16E



Signed by Charles S. Getz  
Surveyor's Michigan License No. 25843

Date June 3, 2000

PEER GROUP APPROVED AT MEETING HELD September 18, 2000. *RUB*