

JAN 19 2001

SECTION

2000 REMONUMENTATION

Re-Mon Liber 2, Page 8

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

20 SEP 2000 2:07 PM

FRANCES L. HOLOWICK
REGISTER OF DEEDS

For corners in

Huron	Located in:	Corner Code #
(County)		
1. Public Land Survey	Sherman T15N R16E	A-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5				4		3		2		1	
3													
4	7	8				9		10		11		12	
5													
6	18	17				16		15		14		13	
7													
8	19	20				21		22		23		24	
9													
10	30	29				28		27		26		25	
11													
12	31	32				33		34		35		36	
13													

I, Charles S. Getz, in a field survey on May 10 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- A-11 1834 G.L.O., H. Parke D.S. County Road Commission Records - Pin, 4" Cedar Post; Iron Pipe Set Post
 - W. Ash 8", S27 1/2°W, 31 Links Recorded Surveys - Case, 6-2-75, Liber 2, Page 366, 3/4" Pipe
 - Lynn 16", N49°W, 58 1/2 Links Little, 5-20-95, Liber 5, Page 159, Pipe
 - L.C.R.C. - NONE Unrecorded Surveys - Case, 9-18-96, Certificate shows Corner
 - County Surveyor Records - NONE Milletics, 4-29-97, 1" Iron Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11
SW Cor, Section 30, T15N-R16E
Found 1" Pipe
Accepted as the best available evidence of the original corner position
(Intersection of Munford Road & Edwards Road)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11
SW Cor, Section 30, T15N-R16E
Found 1" Pipe
N45°W 46.42' to Nail in Telephone Post
N50°E 36.05' to Stop Sign
S45°E 78.15' to Nail in Power Pole
S45°W 35.0' to Stop Sign
South 2629.38' to W 1/4 Cor, Sec 31, T15N-R16E
North 2629.00' to W 1/4 Cor, Sec 30, T15N-R16E



Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date June 3, 2000

PEER GROUP APPROVED AT MEETING
HELD September 18, 2000 RLB