

SURVEY & REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Re: Mon. Liber 1, Page 13

For Corners in **APR 27 1995**

Huron Located in: _____ Corner Code # _____
 (County) **COMMISSION**

1. Public Land survey Sebewaing T 15 N R 9 E J-13 I-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED

13 DEC 94 4:31 P.M.

FRANCES L. HOLIWICK
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, James T. Meek, in a field survey on October, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original Survey, South Bdy. T15N, R9E, 1835, Harvey Parke, D.S.

J-13: South ¼ Corner of Section 35,
 Post
 B. Ash 10", N44°E, 12½ links
 Cedar 10", N78°W, 15 links

I-13: Corner of Sections 34 & 35
 Post
 Hemlock 15", N68°W, 36 links
 Hemlock 8", N77°E, 15 links
 County Surveyors Record: Axle replaced orig. mon
 Huron Survey L 2, Pg 598: 1" steel axle shaft
 Huron Survey L 3, Pg 100: 1" steel axle shaft
 Tuscola Survey, L540, Pg 7: 1" iron rod
 Tuscola Survey, L561, Pg 608: 1" iron bar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13: South ¼ Corner of Section 35,
 There is no remaining evidence of the original corner position.

I-13: Corner of Sections 34 & 35
 Found 1½" iron bar, 2" below grd.
 6'± South of cl Huron Line Rd.
 3'± East of extended cl of Gettel Rd. (N-S)

Accepted as best available evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13: South ¼ Corner of Section 35,
 At proportionate distance;
 Set 'T' iron w/cap #39089, 18" long, 6" below grd.
 from which:
 ½" iron rod, 24" long, S45°E. 15.25'
 NE Cor SE wing wall, S30°W, 13.50'
 SE Cor NE wing wall, N37°W, 24.40'
 ½" iron rod, 24" long, N45°E. 21.30'
 ½" iron w/cap #11192, N90°W, 91.03'
 20.3'± East of concrete bridge pad
 K-13, ½" iron, S89°49'30"E, 2633.80'
 I-13, 1½" iron, N89°49'30"W, 2633.80'

I-13: Corner of Sections 35 & 36
 1½" iron bar, 2" below grd.
 from which:
 Spike in PP, S52°W, 45.30'
 Stop Sign Post, N23°W, 49.93'
 Sign Post (Huron County), N8°E, 80.57'
 Sign post (Weight Limit), S78°E, 56.65'
 ½" iron rod, N90°W, 115.70'
 J-13, T iron, S89°49'30"E, 2633.80'
 H-13, 1½" iron, N89°50'26"W, 2635.91'

Signed by [Signature]
 Surveyor's Michigan License No. 39089

Date 12-12-94

APPROVED AT PEER BOARD MEETING 12-10-94 RLB

