

**SURVEY & REMONUMENTATION**

*Re-Mon. Liller 1, Page 14*

REMONUMENTATION  
APR 27 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in Huron (County) **COMMISSION** Located in: Corner Code #

1. Public Land survey Sebewaing T 15 N R 9 E L-13 K-13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

13 DEC 94 4:32 P.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, James T. Meek, in a field survey on October, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
Original Survey South Bdy. T15NR9E, 1835, Harvey Parke, D.S.

L-13: South ¼ Corner of Section 36,  
Post  
Cedar 11", N37°W, 27 links  
Birch 7", N83°E, 29 links

K-13: Corner of Sections 35 & 36  
Post  
Tamarac 9", N45°W, 15¼ links  
Cedar 7", N68°E, 14¼ links

No County Surveyor's Record  
Huron Survey L 4, Page 650: ¼" pipe

County Surveyors Record: Iron Pin  
Huron Survey L 2, Pg 476: Rerod w/cap #11192  
Huron Survey L 4, Pg 650: ½" iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13: South ¼ Corner of Section 36,  
Found ¼" pipe, 3" below ground  
5'± South of cl Huron Line Rd.  
18'± East of extended cl of ditch(N-S) from South.

K-13: Corner of Sections 35 & 36  
Found ½" iron w/cap #11192, 3" below grd.  
7'± South of cl Huron Line Rd. (E-W)  
8'± West of extended cl of Volz Road(N-S)

Accepted as the best available evidence of original corner position

Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13: South ¼ Corner of Section 36,  
¼" pipe, 3" below grd.  
from which:  
PK nail on SE side of PP, N °E,  
T iron w/cap #39089, S61°E, 19.15'  
T iron w/cap #39089, S66°W, 20.70'  
½" iron, S90°W, 36.31'  
M-13, 1" pipe in mon box, N90°E, 2633.45'  
K-13, ¼" iron w/cap #11192, N89°59'44"W, 2638.93'

K-13: Corner of Sections 35 & 36  
½" iron w/cap #11192, 3" below grd.  
from which:  
Sign Post (Huron County), N20°E, 61.48'  
½" iron (bent), S64°E, 131.92'  
Road Sign post, S63°W, 52.70'  
Tag on PP, N34°W, 70.54'  
L-13, ¼" pipe, S89°59'44"E, 2638.93'  
J-13, T iron, w/cap #39089, N89°49'30"W, 2633.80'

Signed by James T. Meek Date 12-12-94  
Surveyor's Michigan License No. 39089  
APPROVED AT PEER BOARD MEETING, 12-10-94 RLB

