

REMONUMENTATION

OCT 29 1996

COMMISSION

Re-Mon Liber 1, Page 21

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	Brookfield T <u>15 N</u> R <u>10 E</u>	<u>B-13</u>
	T _____ R _____	<u>C-13</u>
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
HURON COUNTY
RECORDED

12 SEP 96 11:22 A.M.

FRANCES L. HOLDWICK
Register of Deeds

I, James T. Meek, in a field survey on August 30, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expessed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T15NR10E, 1835, Harvey Parke, D.S.

B-13: South ¼ Corner of Section 31
Post
Lynn 17", N67°E, 4 links
Cedar 15", N29½°W, 23 links

C-13: Corner of Sections 31 & 32
Post
W. Ash 12", N63°W, 13 links
B. Ash 10", N67½°E, 22 links

No County Surveyor's Record, recorded surveys or LCRC

County Surveyors Record: T iron
Huron Survey L 1, Pg 72: T iron
LCRC, Liber 1, Page 8: T iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13: South ¼ Corner of Section 31

C-13: Corner of Sections 31 & 32

There is no remaining evidence of the original corner position

Found T iron, 6" below grd.
6'+ South of centerline Huron Line Rd.

Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13: South ¼ Corner of Section 31

C-13: Corner of Sections 31 & 32

At proportionate distance,
Set PK nail in concrete bridge deck
From which:
Intersection of SW wing wall and bridge deck
bears North, 1.25' and East, 3.9'
Centerline Huron Line Rd. bears South, 9.0'
Centerline drain bears North
Nail in power pole bears N26°W, 41.7'
½" iron bears S44°W, 16.0'
½" iron bears S14°E, 35.0'
½" iron, N35°E, 38.0'

Set T iron w/cap #39089,
3" below grd. over T iron
From which:
Stop sign post bears S45°E, 37.4'
Nail in power pole bears N42°W, 49.6'
West direction sign post bears N27°E, 33.2'
East direction sign post bears S33°W, 9.6'
½" iron, 3" below grd. bears East, 12.85'

Signed by James T. Meek

Date Sept 6 1996

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 9-9-96 R.L.B.

