

OCT 29 1996

COMMISSION

Re-Mon Liber 1, Page 23

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	Brookfield T <u>15 N</u> R <u>10 E</u>	<u>F-13</u> G-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____

STATE OF MICHIGAN
HURON COUNTY
RECORDED

12 SEP 96 11:22 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James T. Meek, in a field survey on August 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T15NR10E, 1835, Harvey Parke, D.S.

F-13	South ¼ Corner of Section 33 Post Cedar 13", N57½°E, 28 links Maple 24", N57½°W, 28 links	G-13	Corner of Sections 33 and 34 Post Hemlock 17", N43°E, 19 links Sugar Maple 7", N40½°W, 35½ links
	No county surveyors record, recorded surveys or LCRC		County Surveyors Record: Wood post with iron pin, May 16, 1983

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13	South ¼ Corner of Section 33 Found ½" iron flush with the ground At centerline of Huron Line Rd. Accepted as the best available evidence of original corner position	G-13	Corner of Sections 33 and 34 Found ¾" iron in wood post, 7" below grd. Intersection of Brown Rd. and Huron Line Rd. bears East, 3.0'
------	---	------	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13	South ¼ Corner of Section 33 Set ½" iron with cap #39089, 3" below ground From which: Nail in power pole bears North, 39.65' Nail in 16" Walnut bears N64°W, 149.9' ½" iron flush w/grd bears S64°W, 25.0' 1" pipe flush w/grd bears East, 19.31'	G-13	Corner of Sections 33 and 34 Set ½" iron with cap #39089, 3" below ground From which: Nail in power pole bears N25°W, 69.7' Road sign post bears S15°W, 36.0' Huron County sign post bears N20°E, 52.15' Stop sign post bears S30°E, 47.25' ½" iron flush w/grd bears East, 16.11'
------	---	------	---

Signed by James T. Meek
Surveyor's Michigan License No. 39089

Date September 9, 1996

APPROVED AT PEER BOARD MEETING, 9-9-96 RLB

