

SURVEY & REMONUMENTATION

OCT 29 1996

Re-New Liber 1, Page 24

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

	<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	Brookfield T	<u>15 N R 10 E</u>	<u>H-13</u>
		T _____ R _____	<u>I-13</u>
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous	S _____	T _____ R _____	_____

STATE OF MICHIGAN
HURON COUNTY
RECORDED

12 SEP 96 11:22 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James T. Meek, in a field survey on August 30, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T15NR10E, 1835, Harvey Parke, D.S.

H-13 South ¼ Corner of Section 34
Post
Hemlock 8", N75½°E, 42½ links
Beech 10", N43°W, 12 links

No county surveyors record, recorded surveys or LCRC

I-13 Corner of Sections 34 and 35
Post
Beech 13", N62°E, 43 links
Beech 16", N85°W, 21 links

No county surveyors record, recorded surveys or LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 South ¼ Corner of Section 34

Found ½" iron flush with the ground
Centerline of Huron Line Rd. bears North, 1.0'
Lane bears North

Accepted as the best available evidence of original corner position

I-13 Corner of Sections 34 and 35

Found Railroad spike, 4" below grd.
Centerline of Huron Line Rd. bears North, 1.0'

Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 South ¼ Corner of Section 34

Set ½" iron with cap #39089, 3" below ground

From which:
Nail in power pole bears South, 51.5'
Nail in 18" Maple bears S40°W, 31.5'
½" iron flush w/grd bears N58°E, 25.0'
½" iron flush w/grd bears N60°W, 25.0'

I-13 Corner of Sections 34 and 35

Set ½" iron with cap #39089, 3" below ground

From which:
Nail in power pole bears S73°E, 150.2'
Road sign post bears S52°W, 33.1'
West direction sign post bears N13°E, 18.7'
Nail in 14" Walnut bears N80°W, 66.7'

Signed by James T. Meek

Date 9-9-96

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 9-9-96 RLB

