

**SURVEY & REMONUMENTATION**

OCT 29 1996

REMONUMENTATION COMMISSION

*Re-Now Liber 1, Page 24*

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

	<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	Brookfield	T 15 N R 10 E	H-13 I-13
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous	S _____	T _____ R _____	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

12 SEP 96 11:22 A.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James T. Meek, in a field survey on August 30, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
Original Survey South Bdy. T15NR10E, 1835, Harvey Parke, D.S.

H-13 South 1/4 Corner of Section 34  
Post  
Hemlock 8", N75 1/2° E, 42 1/2 links  
Beech 10", N43° W, 12 links

No county surveyors record, recorded surveys or LCRC

I-13 Corner of Sections 34 and 35  
Post  
Beech 13", N62° E, 43 links  
Beech 16", N85° W, 21 links

No county surveyors record, recorded surveys or LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 South 1/4 Corner of Section 34  
  
Found 1/2" iron flush with the ground  
Centerline of Huron Line Rd. bears North, 1.0'  
Lane bears North

Accepted as the best available evidence of original corner position

I-13 Corner of Sections 34 and 35  
  
Found Railroad spike, 4" below grd.  
Centerline of Huron Line Rd. bears North, 1.0'

Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 South 1/4 Corner of Section 34  
  
Set 1/2" iron with cap #39089, 3" below ground

From which:  
Nail in power pole bears South, 51.5'  
Nail in 18" Maple bears S40° W, 31.5'  
1/2" iron flush w/grd bears N58° E, 25.0'  
1/2" iron flush w/grd bears N60° W, 25.0'

I-13 Corner of Sections 34 and 35  
  
Set 1/2" iron with cap #39089, 3" below ground

From which:  
Nail in power pole bears S73° E, 150.2'  
Road sign post bears S52° W, 33.1'  
West direction sign post bears N13° E, 18.7'  
Nail in 14" Walnut bears N80° W, 66.7'

Signed by James T. Meek Date Sept 9 1996

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 9-9-96 RLB

