

OCT 29 1996

COMMISSION REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Re-Monumented, Page 26

For Corners in

Table with columns: Located in: (Huron County), Corner Code #, and survey details (Public Land survey, Property Controlling, Miscellaneous).

STATE OF MICHIGAN HURON COUNTY RECORDED

12 SEP 96 11:23 A.M.

FRANCES L. HOLDWICK REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. ... Recorded Plat ... 5. Private Claims ...

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, James T. Meek, in a field survey on August 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Original Survey South Bdy. T15NR10E, 1835, Harvey Parke, D.S.

L-13 South 1/4 Corner of Section 36 Post Cedar 8", N51°W, 14 1/2 links Cedar 9", N68°E, 6 links No county surveyors record, recorded surveys or LCRC

M-13 Corner of Townships 14 and 15 North, Ranges 10 and 11 East Post Beech 16", N21°W, 28 1/2 links Beech 28", S24°W, 44 links No county surveyors record, recorded surveys or LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 South 1/4 Corner of Section 36 Found 1/2" iron flush w/grd. Intersection of Huron Line Rd. and Trumble Rd. bears North, 3.0' Accepted as the best available evidence of original corner position

M-13 Corner of Townships 14 and 15 North, Ranges 10 and 11 East Found T iron, 2" below grd. At intersection of Huron Line Rd. and Gagetown Rd. Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 South 1/4 Corner of Section 36 Set 1/2" iron with cap #39089, 3" below grd. From which: Underground cable post bears S52°W, 38.3' Road sign post bears N28°W, 38.2' Huron County sign post bears N8°E, 61.6' Road sign post bears S53°E, 17.8' T iron, 1" below grd. bears East 5.01'

M-13 Corner of Townships 14 and 15 North, Ranges 10 and 11 East Set 1/2" iron with cap #39089, 3" below ground over T iron From which: Nail in power pole bears South, 24.2' Nail in power pole bears S80°W, 136.5' 1/2" iron flush w/grd. bears N47°W, 22.0' 1/2" iron flush w/grd. bears N60°E, 40.1'

Signed by [Signature] Date September 9, 1996

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 9-9-96 RLB

