

Common to: M01 - Fair Haven Twp. - T16N-R9E
 M13 - Fair Haven Twp. - T17N-R9E
 A13 - McKinley Twp. - T17N-R10E

Re-Man Liber 1, Page 199
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1998 REMONUMENTATION

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED

For Corners in _____ Located in: _____ Corner Code # _____

Huron (County)

1. Public Land survey Winsor T 16 N R 10 E A-1

2. Property Controlling in Section S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SURVEY & REMONUMENTATION

11 DEC 98 9:45 A.M.

JAN 28 1999

FRANCES L. HOLDWICK
 REGISTER OF DEEDS

SECTION

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	13		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original Survey North Bdy. T16NR10E, 1835, Harvey Parke, D.S.

A-1 Corner of Townships 16 and 17 North, Ranges 9 and 10 East
 Post
 Lynn 14", S47°E, 23 links
 Elm 12", N37°W, 50½ links
 County surveyors record: axle shaft
 Recorded surveys: none
 LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1 Corner of Townships 16 and 17 North, Ranges 9 and 10 East
 Found ¾" iron in mon box
 4' East of CL Bay Port Rd.
 Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 Corner of Townships 16 and 17 North, Ranges 9 and 10 East
 ¾" iron in mon box
 From which:
 Tag in PP bears S70°E, 76.9'
 Tag in 12" Elm bears S40°W, 58.9'
 ½" iron bears N45°W, 28.0'
 ½" iron bears N45°E, 20.0'

Signed by [Signature] Date December 8, 1998
 Surveyor's Michigan License No. 39089



APPROVED AT PEER BOARD MEETING, 11-24-98 RLB