

**SURVEY & REMONUMENTATION**

**JAN 22 1998**

REMONUMENTATION

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Re-Mon Liber 1 Page 128*

For Corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey Winsor	T <u>16 N</u> R <u>10 E</u>	<u>D-13</u>
	T _____ R _____	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

9 DEC 97 11:13 A.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, James T. Meek, in a field survey on October 30, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
Original Survey South Bdy. T16NR10E, 1835, Harvey Parke, D.S.

D-13 South ¼ Corner of Section 32  
Post  
Beech 12", N82°E, 18 links  
Maple 18", N70°W, 26 links  
  
County surveyors record; ¾" iron  
Recorded surveys: none  
LCRC: none

E-13 Corner of Sections 32 and 33  
Post  
Lynn 28", N71°W, 10½ links  
Beech 10", N22°E, 2 links  
  
County surveyors record; ¾" iron  
Recorded surveys: none  
LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 South ¼ Corner of Section 32  
  
Found 1" iron in mon box  
3' South of centerline Kilmanagh Rd.  
Field line bears North  
  
Accepted as the best available evidence of the original corner position.

E-13 Corner of Sections 32 and 33  
  
Found 1" iron in mon box  
At intersection of Kilmanagh & Pobanz Rds.  
  
Accepted as the best available evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 South ¼ Corner of Section 32  
  
1" iron in mon box  
  
From which:  
½" iron w/cap in mon box bears East 6.65'  
½" iron flush w/grd. bears S10°E, 39.5'  
Tag in PP bears S15°W, 38.0'  
Telephone cable box post bears N2°W, 34.5'

E-13 Corner of Sections 32 and 33  
  
Set ½" iron w/cap #39089 over 1" iron in mon box  
From which:  
West leg direct. sign bears N24°E, 37.2'  
Road sign post bears S50°E, 37.4'  
Tag in PP bears S30°W, 46.6'  
½" iron w/cap in mon box bears East, 12.0'

Signed by James T. Meek  
Surveyor's Michigan License No. 39089

Date \_\_\_\_\_

APPROVED AT PEER BOARD MEETING, Nov. 25, 1997 RLB

