

**SURVEY & REMONUMENTATION**

JAN 22 1998

*Re-Mon Liber 1 Page 125*

REMONUMENTATION SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey Winsor	T 16 N R 10 E	<u>J-13</u>
	T R	<u>K-13</u>
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED  
9 DEC 97 11:13 A.M.  
FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, James T. Meek, in a field survey on October 30, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		10		16		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
Original survey south Bdy. T16NR10E, 1835, Harvey Parke, D.S.

J-13 South ¼ Corner of Section 35 Post Elm 22", N87°E, 23 links Hemlock 24", N32°W, 21 links  County surveyors record: ¾" iron in post Recorded surveys: L3, P748; L4, P617 LCRC: none	K-13 Corner of Sections 35 and 36 Post Birch 22", N57°E, 40 links Lynn 7", N64°W, 86 links  County surveyors record: iron in post Recorded surveys: none LCRC: none
-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 South ¼ Corner of Section 35  Found 1" iron in mon box 4' South of centerline Kilmanagh Rd.  Accepted as the best available evidence of the original corner position.	K-13 Corner of Sections 35 and 36  There is no remaining evidence of the original corner position.
-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 South ¼ Corner of Section 35  1" iron in mon box  From which: Tag in PP bears N8°E, 80.5' Tag in PP bears S45°E, 62.' NE corner of house bears S32°W, 72.4' SE corner of house bears N53°W, 97.8'	K-13 Corner of Sections 35 and 36  At proportionate distance Set ½" iron w/cap #39089 in mon box 4' East of intersection Kilmanagh & Notter Rds. From which: Fence post bears N67°E, 42.7' East leg of direct. sign bears S3°W, 17.6' Road sign post bears S37°W, 33.0' Road sign post bears N36°W, 51.25' 1" iron in mon box bears West, 49.6'
--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Signed by [Signature] Date \_\_\_\_\_  
Surveyor's Michigan License No. 39089  
APPROVED AT PEER BOARD MEETING, Nov. 25, 1997 RLD

