

SURVEY & REMONUMENTATION

Re-Mon Liber 1 Page 116

REMONUMENTATION **JAN 22 1998**

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in **SECTION**
Huron Located in: _____ Corner Code # _____
(County)

1. Public Land survey **Oliver** T 16 N R 11 E **J-13**
T _____ R _____ **K-13**
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
HURON COUNTY
RECORDED
9 DEC 97 11:11 A.M.
FRANCES L. HOLWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, James T. Meek, in a field survey on October 30, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T16NR11E, 1835, Harvey Parke, D.S.

<p>J-13 South ¼ Corner of Section 35 Post W. Ash 11", N47°W, 10 links Cedar 6", N84°E, 21½ links</p> <p>County surveyors record: none Recorded surveys: L1, P347 LCRC: none</p>	<p>K-13 Corner of Sections 35 and 36 Post Aspen 9", N84½°E, 28 links Cedar 9", N9°W, 1 links</p> <p>County surveyors record: none Recorded surveys: L3, P362 LCRC: none</p>
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<p>J-13 South ¼ Corner of Section 35</p> <p>Found 1" iron 4' South of centerline Kilmanagh Rd. Occupation line bears North</p> <p>Accepted as the best available evidence of the original corner position.</p>	<p>K-13 Corner of Sections 35 and 36</p> <p>There is no remaining evidence of the original corner position.</p>
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>J-13 South ¼ Corner of Section 35</p> <p>Set ½" iron with cap #39089, 2" below grd., over iron</p> <p>From which: Tag in 6" sq. post bears N11°E, 34.65' Tag in PP bears S57°E, 84.5' Tag in 8" Elm bears S74°W, 78.4' 1" iron bears West, 23.15'</p>	<p>K-13 Corner of Sections 35 and 36</p> <p>At proportionate distance Set ½" iron w/cap #39089 2" below grd. 2' South of int Kilmanagh & Moore Rds. From which: Telephone box bears N33°E, 67.1' East leg of direct sign bears South, 14.4' Road sign post bears S37°W, 32.0' Road sign post bears N18°W, 60.5' ½" iron bears S88°W, 39.6'</p>
---	---

Signed by James I. Meek Date _____
Surveyor's Michigan License No. 39089
APPROVED AT PEER BOARD MEETING, NOV 25, 1997 RLB

