

SURVEY & REMONUMENTATION

JAN 22 1998

Re-Mon Liber 1 Pg. 115

REMONUMENTATION SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

	<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	Oliver	T 16 N R 11 E	L-13
		T _____ R _____	M-13
		T _____ R _____	
		T _____ R _____	
2. Property Controlling in Section	S _____	T _____ R _____	
	S _____	T _____ R _____	
3. Miscellaneous	S _____	T _____ R _____	

STATE OF MICHIGAN
HURON COUNTY
RECORDED

9 DEC 97 11:11 A.M.

FRANCES L. HOLIDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	30							
13													

I, James T. Meek, in a field survey on October 30, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T16NR11E, 1835, Harvey Parke, D.S.

L-13 South ¼ Corner of Section 36
Post
Cedar 8", N74½°E, 9 links
Cedar 7", N34½°W, 8 links

County surveyors record: iron rod
Recorded surveys: L4, P12
LCRC: none

M-13 Corner of Townships 15 and 16 North, Ranges 11 and 12 East
Post
Beech 17", N17°E, 15 links
Beech 17", S30°W, 18 links

County surveyors record: none
Recorded surveys: L4, P12
LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 South ¼ Corner of Section 36
Found ½" iron w/cap #15399
AT centerline of Kilmanagh Rd.

Accepted as the best available evidence of original corner position

M-13 Corner of Townships 15 and 16 North, Ranges 11 and 12 East

Found iron in rock collar, 3' deep
At intersection of Kilmanagh Rd. and Grassmere Rd.

Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 South ¼ Corner of Section 36
½" iron w/cap #15399, 3" below grd.

From which:
Tag in 12" cottonwood bears N1°W, 31.3'
Tag in 9" poplar bears S41°E, 39.4'
Tag in power pole bears S29°W, 57.2'
½" iron, flush w/grd. bears West, 15.25'

M-13 Corner of Townships 15 and 16 North, Ranges 11 and 12 East
Set ½" iron w/cap # 39089 over iron

From which:
Road sign post bears N62°E, 35.7'
½" iron flush w/grd. bears S45°E, 30.0'
Tag in PP bears S47°W, 71.5'
Gas line sign post bears N50°W, 51.85'

Signed by [Signature]

Date _____

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, Nov 25, 1997 RLB

