

*Re-Mon Liber 1, Page 232*

**1998 REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970**

For Corners in OLIVER Township

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>16N</u> R <u>11E</u>	M-1
	T ----- R -----	_____
	T ----- R -----	_____
	T ----- R -----	_____
2. Property Controlling in Section	S _____ T ----- R -----	_____
	S _____ T ----- R -----	_____
3. Miscellaneous Property in Sec.	S _____ T ----- R -----	_____
	S _____ T ----- R -----	_____

**SURVEY &  
 REMONUMENTATION**

JAN 2 8 1999

**SECTION**

STATE OF MICHIGAN  
 HURON COUNTY  
 RECORDED

15 DEC 98 3:34 P.M.

FRANCES L. HOLDWICK  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Russell L. Brown, in a field survey on July 31, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O. H. Parker D.S.; Set as SW Corner Section 31, T17N-R12E.; Hemlock 10, N71W 7.; Hemlock 12, S88E 15  
 County Surveyors Records: NONE  
 County Road Commission Records: Iron Pin; Spike 8" Maple NW 69.60'; Spike 6" Maple NW 46.0'; Spike 8" Maple NW 71.90'; Spike 12" Maple SE 44.0'.  
 Recorded Surveys: NONE  
 Unrecorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories found.  
 Found R.R.S. Removed R.R.S. Set 3/4" x 24" Re-Rod, Reset R.R.S. over 3/4" Re-Rod.  
 Accepted R.R.S. as best evidence of original corner Position.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1, Northeast Corner Section 1, T17N-R11E,  
 R.R.S. over 3/4" x 24" Re-Rod  
 WITNESSES:  
 S45°E 44.18' found Spike in Northeast face 36" Red Maple  
 S70°E 97.76' found Spike in North Face 30" Stump  
 N45°E 35.25' set 1/2" Steel Stake  
 S30°W 41.32' chisled "x" in West End 18" C.M.P.

NOTE:  
 This corner is common with  
 M-13, T17N-R11E,  
 A-13, T17N-R12E,  
 A-1, T16N-R12E,

East 2620.20' to B-13, South 1/4 Corner Section 31, T17N-R12E  
 West 2621.60' to L-13, South 1/4 Corner Section 36, T17N-R11E

Signed by Russell L. Brown Date DEC. 7, 1998  
 Surveyor's Michigan License No. 24588

Peer group approved at meeting held December 8, 1998. *RRB*