

SURVEY & REMONUMENTATION

JAN 22 1998

Re-Mon Liber 1 Page 136

1997 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in COLFAX TOWNSHIP

<u>HURON</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>16</u> N R <u>12</u> E	<u>J-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
HURON COUNTY
RECORDED
12 DEC 97 12:40 P.M.
FRANCES L. HOLIDWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Russell L. Brown, in a field survey on Nov. 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
1834 G.L.O. H. Parke D.S., Set quarter Section Post Beech 28 N50 1/2E 58, B. Ash 9 N78 1/2W 12
COUNTY SURVEYORS RECORDS: None
COUNTY ROAD COMMISSION RECORDS: None
ACT 74 FORM: None
RECORDED SURVEYS: None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

No evidence of original corner or accessories found.
Set 1/2" x 18" Steel Stake by single proportionate measurement between M-13 (S.E. Corner Section 36, T16N-R12E) and T-13 (Corner Sections 34 and 35, T16N-R12E) as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

J-13 S. 1/4 Corner Section 35, T16N-R12E
Set 1/2" x 18" Steel Stake Capped 24588
WITNESSES:
S05°E 37.25' to Spike in E. Side 16" Tree
S65°W 90.24' to P.K. Nail in N.W. Corner Railroad Tie Post
N70°W 64.67' to 1/2" x 18" Steel Stake
N40°E 51.87' to P.K. Nail in N.W. Side P.P.
N80°E 3.52' Found 1/2" Re-Rod apparent North 1/4 Corner Section 2, T15N-R12E
East 2634.62' to S.E. Corner Section 35, T16N-R12E, K-13
West 2634.62' to S.W. Corner Section 35, T16N-R12E, I-13



Signed by Russell L. Brown Date December 9, 1997
Surveyor's Michigan License No. 24588

PEER GROUP APPROVED
AT MEETING HELD
DEC. 11, 1997.
RLB