

**SURVEY & REMONUMENTATION**

JAN 22 1998

*Re-Mon Liber 1 Page 134*

**SECTION**

1997 REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COLFAX TOWNSHIP

<u>HURON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>16</u> N R <u>12</u> E	<u>L-13</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED  
12 DEC 97 12:44 P.M.  
FRANCES L. HOLLOWICK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Russell L. Brown, in a field survey on Nov. 24 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O. H. Parke D.S. Set quarter Section Post  
Cedar 14 N51E 42, B. Ash 9 N69W 12  
COUNTY SURVEYORS RECORDS: None  
COUNTY ROAD COMMISSION RECORDS: None  
ACT 74 FORM: None  
RECORDED SURVEYS: None


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories found.

Set 1/2" x 18" Steel Stake by single proportionate measurement between M-13 (S.E. Corner Section 36, T16N-R12E) and I-13 (Corner Sections 34 and 35, T16N-R12E. as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 S. 1/4 Corner Section 36, T16N-R12E  
Set 1/2" x 18" Steel Stake, Capped 24588  
WITNESSES:  
N65°E 41.98' to 1/2" x 18" Steel Stake  
S65°E 35.03' to 1/2" x 18" Steel Stake  
S65°W 43.64' to 1/2" x 18" Steel Stake  
N65°W 45.88' to 1/2" x 18" Steel Stake  
East 2634.62' to Southeast Corner Section 36, T16N-R12E, M-13  
West 2634.62' to Southwest Corner Section 36, T16N-R12E, K-13



Signed by Russell L. Brown  
Surveyor's Michigan License No. 24588

Date December 9, 1997

PEER GROUP APPROVED  
AT MEETING HELD RLB  
12-11, 1997.