

JAN 22 1998

SECTION

Re Mon. Rehev 1, Page 89

1997 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in VERONA TOWNSHIP

Table with columns: HURON (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

STATE OF MICHIGAN
HURON COUNTY
RECORDED
1 DEC 97 1:51 P.M.
FRANCES L. HOLDWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Russell L. Brown, in a field survey on Oct 15, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked in row 13, column E.

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O. H. Parke D.S. Set Post Corner Section 32 and 33 Cedar 20 N47E 49, Elm 13 N72W 29 1/2
COUNTY SURVEYOR RECORDS: None
ACT 74 FORM: None
COUNTY ROAD COMMISSION RECORDS: Iron Pin, N45°E 52' Face of P.P.A. S45°E 49' Face of P.P., S45°W 42.40' Face of P.P.A.
RECORDED SURVEYS: None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original Corner or Accessories found.
Re-established Corner position by proportionate measurement to G.L.O. Notes, between Corner F-13 (South 1/4 Corner Section 33) and Corner C-13 (Corner Sections 31 and 32) as best evidence of original Corner position for Corner E-13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corners Sections 32 and 33, T16N-R13E, E-13
Set 1/2" x 18" Steel Stake capped 24588
WITNESSES:
S05°E 34.51' to P.K. Nail in East Side Brace Pole
S55°E 75.39' to Spike in North Side Power Pole
N55°E 77.44' to Spike in Southeast Side Brace Pole
N55°W 35.54' to 1/2" x 18" Steel Stake
East 30.72' to 3/4" Steel Stake apparent Corner Sections 4 and 5, T15N-R13E
East 2639.54' to South 1/4 Corner Section 33, T16N-R13E
West 2629.35' to South 1/4 Corner Section 32, T16N-R13E



Signed by Russell L. Brown Date Nov. 3, 1997
Surveyor's Michigan License No. 24588

PEER GROUP APPROVED
AT MEETING HELD
Nov 25, 1997. RLB