

**SURVEY & REMONUMENTATION**

JAN 22 1998

*Re Nova Liber 1, Page 92*

1997 REMONUMENTATION

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in VERONA TOWNSHIP

<u>HURON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>16N</u> R <u>13E</u>	H-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

1 DEC 97 1:51 P.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Russell L. Brown, in a field survey on Oct. 16, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 1834 G.L.O. H. Parke D.S. Set quarter Section Post  
 Hemlock 16 N73 1/2 E 27.1/2, Do 10 N24 1/2W 15 1/2  
 COUNTY SURVEYOR RECORDS: None  
 ACT 74 FORM: None  
 COUNTY ROAD COMMISSION: Cedar Post-in line with Fence North  
 Spike 18" Lombardi, South 30.0, Spike 18" Lombardi, S40E 36.8  
 RECORDED SURVEYS: None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 No evidence of original Corner or accessories found.  
 Found 1/2" Re-rod with cap in centerline gravel road East and West (Helena Road) and in line with Fence Corner Post and occupational line to North.  
 Accepted 1/2" Capped Re-rod as the best evidence of original Corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 S. 1/4 Corner Section 34, T16N-R13E, H-13  
 Found 1/2" Capped Re-rod

WITNESSES:  
 S30°E 27.85' to V Notch in Southerly End 24" C.M.P.  
 N60°W 55.30' to Spike in Power Pole  
 North 49.05' to Spike in Corner Post  
 North 52.68' to Spike in East Side 10" Elm Tree  
 S45°W 43.48' to Notch West End 15" C.M.P.  
 East 2643.67' to Southeast Corner Section 34, T16N-R13E  
 West 2651.12' to Southwest Corner Section 34, T16N-R13E



Signed by Russell L. Brown Date Nov. 3, 1997  
 Surveyor's Michigan License No. 24588

PEER GROUP APPROVED  
 AT MEETING HELD  
Nov 25, 1997 RLB