

SURVEY & REMONUMENTATION

JAN 22 1998

Re-Monumentation, Page 101

SECTION

1997 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SIGEL TOWNSHIP

<u>HURON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>16N</u> R <u>14E</u>	<u>B-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED
 1 DEC 97 1:53 P.M.
 FRANCES L. HOLDWICK
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Russell L. Brown, in a field survey on Oct 22, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 1834 G.L.O. H. Parke D.S. Set quarter Section Post
 Beech 24 N61E 111 1/2, Sugar 7 N66 1/2W 35
 COUNTY SURVEYOR RECORDS: None
 ACT 74 FORM: None
 COUNTY ROAD COMMISSION RECORDS: None
 RECORDED SURVEYS: None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No evidence of original corner or accessories found.
 Set 1/2" x 18" Steel Stake by single proportionate measurement on line between A-13 (Southwest Corner Section 31, T16N-R14E) and C-13 (Southeast Corner Section 31, T16N-R14E) as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 South 1/4 Corner Section 31, T16N-R14E, B-13
 Set 1/2" x 18" Steel Stake capped 24588
 WITNESSES:
 S50°E 25.97' to 1/2" x 18" Steel Stake
 S50°W 27.71' to 1/2" x 18" Steel Stake
 N45°W 29.89' to 1/2" x 18" Steel Stake
 N40°E 30.76' to Notch West End 15" C.M.P.
 East 2645.74' to Southeast Corner Section 31, T16N-R14E, C-13
 West 2751.57' to Southwest Corner Section 31, T16N-R14E, A-13



Signed by Russell L. Brown
 Surveyor's Michigan License No. 24588

Date Nov. 3, 1997

PEER GROUP APPROVED
 AT MEETING HELD
Nov. 25, 1997. RLB