

*Re-Mon., Liber 1, Page 177*

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Huron (County)	Located in:	Corner Code #
1. Public Land Survey	Sand Beach T16N R15E	A-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
 HURON COUNTY  
 RECORDED

25 NOV 98 10:08 A.M.

FRANCES L. HOLDWICK  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Charles S. Getz, in a field survey on Nov. 04, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2	6			5			4		3			2	1
3													
4	7			8			9		10			11	12
5													
6	18			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29			28		27			26	25
11													
12	31			32			33		34			35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-1  
 1834 G.L.O., H. Parke D.S. County Surveyor Records - NONE  
 Post County Road Commission Records - Iron Pin in Cedar Post  
 Maple 11", S12°E, 11 Links Recorded Surveys - Survey Liber 3, Page 597, 3/4" steel pin in mon. box in place.  
 Hemlock 9", N28°W, 16 1/2 Links Unrecorded Surveys - NONE  
 L.C.R.C. - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1  
 NW Cor, Section 6, T16N-R15E  
 Found 3/4" Iron Bar in Monument Box  
 Accepted as the best available evidence of original corner position  
 (Intersection of Rapson & Finkel Roads)


SURVEY &  
 REMONUMENTATION

JAN 28 1999

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1  
 NW Cor, Section 6, T16N-R15E  
 Found 3/4" Iron Bar in Monument Box  
 N50°W 69.0' to Nail in Power Pole  
 N45°E 58.70' to Buried Cable Sign  
 S45°E 51.55' to Road Sign  
 S60°W 43.40' to Stop Sign  
 West 2630.00' to S 1/4 Cor, Sec 36, T17N-R14E  
 East 2631.89' to S 1/4 Cor, Sec 31, T17N-R15E



Signed by: Charles S. Getz  
 Surveyor's Michigan License No. 25843

Date November 8, 1998

PEER GROUP APPROVED AT  
 MEETING 11-24-98 RLB