

*Common to A01 - Sherman Twp. - T15N-R15E
 *Common to M01 - Paris Twp. - T15N-R14E
 *Common to M13 - Sigel Twp. - T16N-R14E

SURVEY & REMONUMENTATION

REMONUMENTATION

Re-Monument 1, Page 67

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

JAN 22 1998

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED

For corners in

6 NOV 97 10:25 A.M.

FRANCES L. HOLDWICK
 REGISTER OF DEEDS

<u>Huron</u> SECTION (County)	Located In:	Corner Code #
1. Public Land Survey Sand Beach	T16N R 15E	<u>A-13</u> B-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Charles S. Getz, in a field survey on Aug. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-13
 1834 G.L.O., H. Parke D.S.
 Post
 Pine 18", S84°W, 8 Links
 B. Ash 16", N81½°E, 21 Links

Co. Surveyor Records - NONE, Co. Rd. Comm. Records - Iron Rod
 Recorded Surveys - NONE, Huron Surveying 10-25-76 - 3/4" Pin
 L.C.R.C. 1994 Remonumentation - Monument Box

B-13
 1834 G.L.O., H. Parke D.S.
 Quarter Section Corner
 Cedar 9 inches diameter Corner Tree

Co. Surveyor Records - NONE, Co. Rd. Comm. Records - Iron Rod
 Recorded Surveys - NONE, Unrecorded Surveys - NONE
 L.C.R.C. - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13
 SW Cor, Section 31, T16N-R15E
 Found 3/4" Re-Rod in Monument Box
 Accepted as the best available evidence of original corner position
 (Intersection of Helena & Finkel Roads)

B-13
 S 1/4 Cor, Section 31, T16N-R15E
 Found no evidence of original corner position.
 Re-established corner position by proportionate measure from G.L.O. Notes, between C-13 and A-13 as best evidence of original corner position for B-13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13
 SW Cor, Section 31, T16N-R15E
 Found 3/4" Re-Rod in Monument Box
 N45°W 71.35' to Spike in Power Pole
 S45°W 66.66' to Spike in Power Pole
 S45°E 64.50' to Spike in Tele Box Post
 N30°E 89.22' to PK Nail in W. side of Power Pole
 South 2693.94' to W 1/4 Cor, Sec 6, T15N-R15E
 East 2479.79' to S 1/4 Cor, Sec 31, T16N-R15E

B-13
 S 1/4 Cor, Section 31, T16N-R15E
 Set 1/2" Re-Rod in Monument Box (Capped)
 North 51.66' Nail in E. Side of Power Pole
 West 69.27' to Monument Box
 N05°W 33.84' to Notch in Top of 36" Culvert
 S10°W 35.83' to Notch in Top of 36" Culvert
 N45°W 73.51' to SE Cor of Tele Box
 West 2479.79' to SW Cor, Sec 31, T16N-R15E
 East 2615.81' to SE Cor, Sec 31, T16N-R15E

Signed by Charles S. Getz
 Surveyor's Michigan License No. 25843

Date October 12, 1997

PEER GROUP APPROVED AT MEETING

NOVEMBER 5, 1997

RLB

