

SURVEY & REMONUMENTATION

JAN 22 1998

Re-Monument 1, Page 67

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

STATE OF MICHIGAN HURON COUNTY RECORDED

6 NOV 97 10:25 A.M.

FRANCES L. HOLDWICK REGISTER OF DEEDS

Huron (County) Located In: Corner Code # 1. Public Land Survey Sand Beach T16NR 15E A-13 B-13 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. , Recorded Plat 5. Private Claims

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, Charles S. Getz, in a field survey on Aug. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13 1834 G.L.O., H. Parke D.S. Post Pine 18", S84°W, 8 Links B. Ash 16", N81 1/2°E, 21 Links Co. Surveyor Records - NONE, Co. Rd. Comm. Records - Iron Rod Recorded Surveys - NONE, Huron Surveying 10-25-76 - 3/4" Pin L.C.R.C. 1994 Remonumentation - Monument Box B-13 1834 G.L.O., H. Parke D.S. Quarter Section Corner Cedar 9inches diameter Corner Tree Co. Surveyor Records - NONE, Co. Rd. Comm. Records - Iron Rod Recorded Surveys - NONE, Unrecorded Surveys - NONE L.C.R.C. - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 SW Cor, Section 31, T16N-R15E Found 3/4" Re-Rod in Monument Box Accepted as the best available evidence of original corner position (Intersection of Helena & Finkel Roads) B-13 S 1/4 Cor, Section 31, T16N-R15E Found no evidence of original corner position. Re-established corner position by proportionate measure from G.L.O. Notes, between C-13 and A-13 as best evidence of original corner position for B-13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 SW Cor, Section 31, T16N-R15E Found 3/4" Re-Rod in Monument Box N45°W 71.35' to Spike in Power Pole S45°W 66.66' to Spike in Power Pole S45°E 64.50' to Spike in Tele Box Post N30°E 89.22' to PK Nail in W. side of Power Pole South 2693.94' to W 1/4 Cor, Sec 6, T15N-R15E East 2479.79' to S 1/4 Cor, Sec 31, T16N-R15E B-13 S 1/4 Cor, Section 31, T16N-R15E Set 1/2" Re-Rod in Monument Box (Capped) North 51.66' Nail in E. Side of Power Pole West 69.27' to Monument Box N05°W 33.84' to Notch in Top of 36" Culvert S10°W 35.83' to Notch in Top of 36" Culvert N45°W 73.51' to SE Cor of Tele Box West 2479.79' to SW Cor, Sec 31, T16N-R15E East 2615.81' to SE Cor, Sec 31, T16N-R15E

Signed by Charles S. Getz Surveyor's Michigan License No. 25843

Date October 12, 1997

PEER GROUP APPROVED AT MEETING NOVEMBER 5, 1997 RLB

