

SURVEY & REMONUMENTATION

JAN 22 1998

REMONUMENTATION

Re Mon Liber 1, Page 68

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Huron (County)	Located In:	Corner Code #
1. Public Land Survey Sand Beach	T16N R15E	E-13
	T R	F-13
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
HURON COUNTY
RECORDED

6 NOV 97 10:25 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Charles S. Getz, in a field survey on Aug. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13 1834 G.L.O., H. Parke D.S. Set Post Elm 18", N29°E, 17 Links Birch 12", N56°W, 30 Links	Co. Surveyor Records - NONE, Recorded Surveys - NONE Co. Road Comm. Records - Axle in Cedar Post Huron Surveying 4-1-80 - Axle Shaft in Monument Box L.C.R.C. - NONE
F-13 1834 G.L.O., H. Parke D.S. Set quarter section post Hemlock 8", N83°E, 27 Links Birch 14", N11½°W, 41 Links	Co. Surveyor Records - NONE, Recorded Surveys - NONE Co. Road Comm. Records - Axle Huron Surveying 5-2-90 - Certificate shows corner L.C.R.C. - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 SW Cor, Section 33, T16N-R15E Found Axle Shaft in Monument Box Accepted as the best available evidence of original corner position (Intersection of Helena & Eppenbrock Roads)	F-13 S 1/4 Cor, Section 33, T16N-R15E Found Axle Shaft in Monument Box Accepted as the best available evidence of original corner position
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 SW Cor, Section 33, T16N-R15E Found Axle Shaft in Monument Box West 77.23' to Axle Shaft in Monument Box N45°E 62.12' to Nail in SE Side of Power Pole N45°W 59.90' to Nail in SE Side of Tele Box Post S30°W 56.20' to Nail in E. Side of Power Pole North 1.4' to Centerline of Pavement West 2622.66' to S 1/4 Cor, Sec 32, T16N-R15E East 2607.88' to S 1/4 Cor, Sec 33, T16N-R15E	F-13 S 1/4 Cor, Section 33, T16N-R15E Found Axle Shaft in Monument Box N30°E 70.32' to Nail in NE Side of Power Pole S10°E 39.86' to Nail in W. Side of 18" Cedar S30°W 45.65' to Nail in NW Side of 36" Maple S45°W 60.54' to Nail in NW Side of 12" Pine West 2607.88' to SW Cor, Sec 33, T16N-R15E East 2594.68' to SE Cor, Sec 33, T16N-R15E
--	--

Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date October 12, 1997

PEER GROUP APPROVED AT
MEETING NOVEMBER 5, 1997.
RLB

