

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

REMONUMENTATION

Re Mon Liber 1, Page 69

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| Huron (County) | Located In: | Corner Code # |
|------------------------------------|----------------|---------------|
| 1. Public Land Survey Sand Beach | T16N R15E | G-13 |
| | T___ R___ | H-13 |
| | T___ R___ | |
| | T___ R___ | |
| 2. Property Controlling in Section | S___ T___ R___ | |
| | S___ T___ R___ | |
| 3. Miscellaneous Property in Sec. | S___ T___ R___ | |
| | S___ T___ R___ | |

STATE OF MICHIGAN
HURON COUNTY
RECORDED

6 NOV 97 10:25 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Charles S. Getz, in a field survey on Aug. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

G-13 1834 G.L.O., H. Parke D.S.
Set Post
Cedar 20", East, 17 Links
Birch 9", N73°W, 15 Links

Co. Surveyor Records - NONE, Survey Liber 2, Page 72 - Axle
Co. Rd. Comm. Records - Axle
Huron Surveying 5-2-90 - Certificate shows corner
L.C.R.C. - NONE

H-13 1834 G.L.O., H. Parke D.S.
Set quarter section post
Hemlock 10", N86°E, 17½ Links
Cedar 5", N69°W, 26 Links

Co. Surveyor Records - NONE, Survey Liber 2, Page 72 - 1" Pin in post, Survey Liber 3, Page 669 - Monument Box
Co. Rd. Comm. Records - 1" Iron Pin in Post
Huron Surveying 10-7-96 - Monument Box, L.C.R.C. - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13
SW Cor, Section 34, T16N-R15E
Found Axle Shaft in Monument Box
Accepted as the best available evidence of original corner position
(Intersection of Helena & Buhl Roads)

H-13
S 1/4 Cor, Section 34, T16N-R15E
Found 1" Pipe in Monument Box
Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13
SW Cor, Section 34, T16N-R15E
Found Axle Shaft in Monument Box
West 31.42' to 2" Pipe in Monument Box
N60°W 93.95' to Nail in S. Side of Power Pole
N30°W 64.02' to Nail in Anchor Pole
N45°E 66.72' to Nail in NW Side of 18" Oak
N30°E 97.45' to Nail in NW Side of 30" Chestnut
West 2594.68' to S 1/4 Cor, Sec 33, T16N-R15E
East 2631.84' to S 1/4 Cor, Sec 34, T16N-R15E

H-13
S 1/4 Cor, Section 34, T16N-R15E
Found 1" Pipe in Monument Box
West 19.90' to PK Nail
N15°W 40.83' to Spike in E. Side of Power Pole
S15°W 57.90' to NE Corner of House
S45°E 81.68' to Nail in N. Side of Power Pole
N55°W 94.82' to SE Corner of Church
West 2631.84' to SW Cor, Sec 34, T16N-R15E
East 2636.84' to SE Cor, Sec 34, T16N-R15E

Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date October 12, 1997

PEER GROUP APPROVED AT MEETING November 5, 1997
RLB

