

**SURVEY & REMONUMENTATION**

JAN 22 1998

SECTION

REMONUMENTATION

*Re Man Liber 1, Page 69*

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Huron (County)	Located In:	Corner Code #
1. Public Land Survey Sand Beach	T16N R15E	G-13 H-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED  
6 NOV 97 10:25 A.M.  
FRANCES L. HOLDWICK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Charles S. Getz, in a field survey on Aug. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-13 1834 G.L.O., H. Parke D.S. Co. Surveyor Records - NONE, Survey Liber 2, Page 72 - Axle  
Set Post Co. Rd. Comm. Records - Axle  
Cedar 20", East, 17 Links Huron Surveying 5-2-90 - Certificate shows corner  
Birch 9", N73°W, 15 Links L.C.R.C. - NONE

H-13 1834 G.L.O., H. Parke D.S. Co. Surveyor Records - NONE, Survey Liber 2, Page 72 - 1" Pin in  
Set quarter section post post, Survey Liber 3, Page 669 - Monument Box  
Hemlock 10", N86°E, 17 1/2 Links Co. Rd. Comm. Records - 1" Iron Pin in Post  
Cedar 5", N69°W, 26 Links Huron Surveying 10-7-96 - Monument Box, L.C.R.C. - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13  
SW Cor, Section 34, T16N-R15E  
Found Axle Shaft in Monument Box  
Accepted as the best available evidence  
of original corner position  
(Intersection of Helena & Buhl Roads)

H-13  
S 1/4 Cor, Section 34, T16N-R15E  
Found 1" Pipe in Monument Box  
Accepted as the best available evidence  
of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13  
SW Cor, Section 34, T16N-R15E  
Found Axle Shaft in Monument Box  
West 31.42' to 2" Pipe in Monument Box  
N60°W 93.95' to Nail in S. Side of Power Pole  
N30°W 64.02' to Nail in Anchor Pole  
N45°E 66.72' to Nail in NW Side of 18" Oak  
N30°E 97.45' to Nail in NW Side of 30" Chestnut  
West 2594.68' to S 1/4 Cor, Sec 33, T16N-R15E  
East 2631.84' to S 1/4 Cor, Sec 34, T16N-R15E

H-13  
S 1/4 Cor, Section 34, T16N-R15E  
Found 1" Pipe in Monument Box  
West 19.90' to PK Nail  
N15°W 40.83' to Spike in E. Side of Power Pole  
S15°W 57.90' to NE Corner of House  
S45°E 81.68' to Nail in N. Side of Power Pole  
N55°W 94.82' to SE Corner of Church  
West 2631.84' to SW Cor, Sec 34, T16N-R15E  
East 2636.84' to SE Cor, Sec 34, T16N-R15E

Signed by Charles S. Getz  
Surveyor's Michigan License No. 25843

Date October 12, 1997

PEER GROUP APPROVED AT  
MEETING NOVEMBER 5, 1997  
RLB

