

**SURVEY &  
REMONUMENTATION**

JAN 22 1998

SECTION

REMONUMENTATION

*Re Mon Liber 1, Page 71*

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey Sand Beach	T16N R15E	K-13 L-13
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

6 NOV 97 10:26 A.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11				
5													
6	18		17		16		15		14				
7													
8	19		20		21		22		23				
9													
10	30		29		28		27		26				
11													
12	31		32		33		34		35				
13													

I, Charles S. Getz, in a field survey on Aug. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 1834 G.L.O., H. Parke D.S. Set Post Hemlock 20", N44½°E, 48 Links Do. 8", N74½°W, 11 Links	Co. Surveyor Records - NONE, Co. Rd. Comm. Records - Axle Survey Liber 4, Page 97 - Monument Box Huron Surveying 2-25-80 - Monument Box L.C.R.C. - NONE
L-13 G.L.O., H. Parke D.S. (1834) Set quarter section post Hemlock 12", N63°W, 14 Links Cedar 8", N41°E, 24 Links	Co. Surveyor Records - NONE, Co. Rd. Comm. Records - NONE Recorded Surveys - NONE Huron Surveying 2-25-80 - PK Nail L.C.R.C. - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 SW Cor, Section 36, T16N-R15E Found 3/4" Iron Bar in Monument Box Accepted as the best available evidence of original corner position (Intersection of Helena & Schock Roads)	L-13 S 1/4 Cor, Section 36, T16N-R15E Found PK Nail as per Survey by Huron Surveying, Inc. dated 02-25-80 Accepted as the best available evidence of original corner position
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 SW Cor, Section 36, T16N-R15E Found 3/4" Iron Bar in Monument Box West 78.50' to Axle Shaft in Monument Box N45°W 72.33' to Nail in SW Side of Power Pole S45°W 59.10' to Nail in NW Side of Power Pole S45°E 72.05' to Nail in N. Side of Fence Post N45°E 64.77' to SW Cor of Tele Box West 2586.72' to S 1/4 Cor, Sec 35, T16N-R15E East 2640.76' to S 1/4 Cor, Sec 36, T16N-R15E	L-13 S 1/4 Cor, Section 36, T16N-R15E Set 1/2" Iron Bar in Monument Box (Capped) West 47.80' to Axle Shaft in Monument Box S35°E 71.70' to Center of 4" Well S80°E 56.0' to Mailbox Post (Hse #9266) S40°W 57.98' to Spike in NW Side of Power Pole West 2640.76' to SW Cor, Sec 36, T16N-R15E East 2625.24' to SE Cor, Sec 36, T16N-R15E
--	---

Signed by Charles S. Getz  
Surveyor's Michigan License No. 25843

Date October 12, 1997

PEER GROUP APPROVED AT  
MEETING November 5, 1997  
RLB

