

*Common to A13 - Sand Beach Twp. - T16N-R16E.
 *Common to A01 - Sherman Twp. - T15N-R16E
 *Common to M01 - Sherman Twp. - T15N-R15E

Re-Monumented, Page 72

REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey Sand Beach	T16N R15E	M-13 ✓
	T15N R15E	M-1
	T16N R16E	A-13
	T15N R16E	A-1
2. Property Controlling in Section	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED

6 NOV 97 10:26 A.M.

FRANCES L. HOLIDWICK
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Charles S. Getz, in a field survey on Aug. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-13 1834 G.L.O., H. Parke D.S. Post Hemlock 14", S28°W, 30 Links Do. 8", N31°E, 8 Links	Co. Surveyor Records - NONE, Co. Rd. Comm. Records - Iron Pin Survey Liber 3, Page 425 - 3/4" Re-Rod in Monument Box Unrecorded Surveys - NONE L.C.R.C. - NONE
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13
 SE Cor, Section 36, T16N-R15E
 Found 3/4" Re-Rod in Monument Box
 Accepted as the best available evidence
 of original corner position
 (Intersection of Helena & Edwards Roads)

SURVEY &
 REMONUMENTATION


JAN 22 1998

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13
 SE Cor, Section 36, T16N-R15E
 (Found 3/4" Re-Rod in Monument Box)
 N45°E 74.88' to Nail in SE Side of Power Pole
 S45°E 57.81' to Nail in NE Side of Cable Post
 N40°W 51.53' to S. Point of Conc. Project Marker
 West 2625.24' to S 1/4 Cor, Sec 36, T16N-R15E
 East 2623.54' to S 1/4 Cor, Sec 31, T16N-R16E

Signed by Charles S. Getz
 Surveyor's Michigan License No. 25843



Date October 12, 1997

PEER GROUP APPROVED AT
 MEETING NOVEMBER 5, 1997
 RLB

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995