

JAN 19 2001

Re-Mon. Liber 2, Page 56

2000 REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Huron (County)	Located In:	Corner Code #
1. Public Land Survey Sand Beach	T16N R15E	A-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

20 SEP 2000 2:01 PM

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2			1
3												
4	7		8		9		10		11			1
5												
6	18		17		16		15		14			1
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

I, Charles S. Getz, in a field survey on May 17, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


A-2 1834 G.L.O., H. Parke D.S. County Road Commission Records - Iron Pin  
Set quarter section post  
Hemlock 7", S47°W, 7 Links Recorded Surveys - NONE  
Beech 7", N23°W, 18½ Links Unrecorded Surveys - NONE  
L.C.R.C. - NONE  
County Surveyor Records - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2  
W 1/4 Cor, Section 6, T16N-R15E  
Found 3/4" Iron Bar  
Accepted as the best available evidence of the original corner position  
(On Finkel Road)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2  
W 1/4 Cor, Section 6, T16N-R15E  
Found 3/4" Iron Bar  
N40°W 65.60' to Nail in Large Power Pole  
N50°W 56.55' to Nail in Large Power Pole  
S50°W 39.90' to Metal Post  
North 2621.04' to NW Cor, Sec 6, T16N-R15E  
South 2637.17' to SW Cor, Sec 6, T16N-R15E



Signed by Charles S. Getz  
Surveyor's Michigan License No. 25843

Date June 10, 2000

PEER GROUP APPROVED AT MEETING  
HELD September 18, 2000. RLB