

Re-Mon Liber 1, Page 196

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

For Corners in

	<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	Fairhaven	T <u>16</u> N R <u>9</u> E	H-13 ✓ I-13 ✓
		T _____ R _____	
		T _____ R _____	
		T _____ R _____	
2. Property Controlling in Section	S _____	T _____ R _____	
	S _____	T _____ R _____	
3. Miscellaneous	S _____	T _____ R _____	

SURVEY &
REMONUMENTATION

11 DEC 98 9:45 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

JAN 28 1999

SECTION

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		6		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original survey South Bdy. T16NR9E, 1835, Harvey Parke, D.S.

H-13	South ¼ Corner of Section 34 Post Elm 18", N26°E, 16½ links Maple 24", N59°W, 33½ links County surveyors record; 1" pin Recorded surveys: none LCRC: none	I-13	Corner of Sections 34 and 35 Post Sugar 12", N62½°E, 6 links Lynn 17", N71°W, 52 links County surveyors record; iron pin Recorded surveys: none LCRC: none
------	---	------	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13	South ¼ Corner of Section 34 Found 1" iron Accepted as the best available evidence of the original corner position.	I-13	Corner of Sections 34 and 35 Found ¾" iron in mon box At intersection of Kilmanagh & Kuhl Rds. Accepted as the best available evidence of the original corner position.
------	---	------	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13	South ¼ Corner of Section 34 1" iron in mon box From which: Tag in wood post bears N47°E, 45.6' ½" iron bears S45°E, 25.0' ½" iron bears S45°W, 20.0' ½" iron bears N45°W, 24.0'	I-13	Corner of Sections 34 and 35 ¾" iron in mon box From which: Road sign post bears N52°E, 115.5' East leg of direction sign bears S18°W, 16.6' Road sign post bears S86°W, 102.0' Telephone box bears N72°W, 27.1'
------	--	------	--

Signed by [Signature] Date December 8, 1998
Surveyor's Michigan License No. 39089



APPROVED AT PEER BOARD MEETING, 11-24-98 RAB

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN 28 1999