

Common to: MI3 - Fair Haven Twp. - T17N-R9E  
 A13 - McKinley Twp. - T17N-R10E  
 A01 - Winsor Twp. - T16N-R10E

*Re-Mon Survey 1, Page 192*

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in  
Huron Located in: Corner Code #  
 (County)

1. Public Land survey Fairhaven T 16 N R 9 E M-1  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 HURON COUNTY  
 RECORDED  
 11 DEC 98 9:44 A.M.  
 FRANCES L. HOLDWICK  
 REGISTER OF DEEDS

**SURVEY & REMONUMENTATION**  
**JAN 28 1999**  
**SECTION**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 Original Survey North Bdy. T16NR9E, 1835, Harvey Parke, D.S.


M-1 Corner of Townships 16 and 17 North, Ranges 9 and 10 East  
 Post  
 Lynn 14", S47°E, 23 links  
 Elm 12", N37°W, 50½ links  
 County surveyors record: axle shaft  
 Recorded surveys: none  
 LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 Corner of Townships 16 and 17 North, Ranges 9 and 10 East  
 Found ¾" iron in mon box  
 4' East of CL Bay Port Rd.  
 Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 Corner of Townships 16 and 17 North, Ranges 9 and 10 East  
 ¾" iron in mon box  
 From which:  
 Tag in PP bears S70°E, 76.9'  
 Tag in 12" Elm bears S40°W, 58.9'  
 ½" iron bears N45°W, 28.0'  
 ½" iron bears N45°E, 20.0'



Signed by [Signature] Date December 8, 1998

Surveyor's Michigan License No. 39089  
 APPROVED AT PEER BOARD MEETING, 11-24-98 RJB