

Re Mon Liber 1, Page 188

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

For Corners in

Huron
(County)

Located in:

Corner Code #

SURVEY &
REMONUMENTATION

11 DEC 98 9:43 A.M.

- 1. Public Land survey McKinley T 17 N R 10 E
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____

- B-13
- C-13
- _____
- _____
- _____
- _____

JAN 8 1999

FRANCES L. HOLDWICK
REGISTER OF DEEDS

SECTION

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T17NR10E, 1835, Harvey Parke, D.S.

B-13 South ¼ Corner of Section 31
Post
Pine 30", N33°E, 9½ links
Sugar 14", N63°W, 62 links

County surveyors record; none
Recorded surveys; none
No ICRC

C-13 Corner of Sections 31 and 32
Post
Cedar 20", N33°E, 9½ links
W. Oak 26", N23°W, 11½ links

County Surveyors Record: none
Recorded surveys; none
No ICRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 South ¼ Corner of Section 31

There is no remaining evidence of the original corner position.

C-13 Corner of Sections 31 and 32

There is no remaining evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 South ¼ Corner of Section 31

At proportionate distance

Set ½" iron w/cap #39089

From which:
½" iron bears N45°E, 15.0'
½" iron bears S45°E, 10.0'
½" iron bears S45°W, 40.0'
½" iron bears N45°W, 27.0'

C-13 Corner of Sections 31 and 32

At proportionate distance

Set ½" iron w/cap #39089

From which:
Centerline of gravel road bears West, 2.0'
Tag on Triple Cottonwood bears S58°W, 51.6'
Tag on 6" Willow bears S64°W, 49.8'

Signed by James T. Meek

Date December 8, 1998

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 11-24-98 RLB



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN 28, 1998