

Re Mon Liber 1, Page 188

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

For Corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	McKinley T <u>17 N</u> R <u>10 E</u>	<u>B-13</u>
	T _____ R _____	<u>C-13</u>
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous	S _____ T _____ R _____	

SURVEY &
REMONUMENTATION
JAN 28 1999
SECTION

11 DEC 98 9:43 A.M.
FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5		4		3		2		1		
3												
4	7	8		9		10		11		12		
5												
6	18	17		16		15		14		13		
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		
13												

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T17NR10E, 1835, Harvey Parke, D.S.

B-13 South 1/4 Corner of Section 31 Post Pine 30", N33°E, 9 1/2 links Sugar 14", N63°W, 62 links County surveyors record; none Recorded surveys; none No LCRC	C-13 Corner of Sections 31 and 32 Post Cedar 20", N33°E, 9 1/2 links W. Oak 26", N23°W, 11 1/2 links County Surveyors Record: none Recorded surveys; none No LCRC
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 South 1/4 Corner of Section 31 There is no remaining evidence of the original corner position.	C-13 Corner of Sections 31 and 32 There is no remaining evidence of the original corner position.
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 South 1/4 Corner of Section 31 At proportionate distance Set 1/2" iron w/cap #39089 From which: 1/2" iron bears N45°E, 15.0' 1/2" iron bears S45°E, 10.0' 1/2" iron bears S45°W, 40.0' 1/2" iron bears N45°W, 27.0'	C-13 Corner of Sections 31 and 32 At proportionate distance Set 1/2" iron w/cap #39089 From which: Centerline of gravel road bears West, 2.0' Tag on Triple Cottonwood bears S58°W, 51.6' Tag on 6" Willow bears S64°W, 49.8'
---	---

Signed by James T. Meek
Surveyor's Michigan License No. 39089

Date December 8, 1998

APPROVED AT PEER BOARD MEETING, 11-24-98 RLB

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS

